

Project Facts

Plaza Reconstruction Southfield Plaza Pavilion



Location: Southfield, MI
Cost: \$1,331,000
Start Date: August, 2006
Duration: Four Months



Services Provided

- Demolition and removal
- Pedestal positioning
- Paver installation
- Replace drains
- Replace membranes

Project Description

An existing 80,000 square foot concrete plaza with fluid applied membrane and a protection course under the slab required restoration. Western completely removed the existing concrete slab and membrane. A new membrane was installed followed by positioning of pedestals and installation of 2' x 2' concrete pavers. Western also removed and replaced all drains and waterproof membranes in the existing planters. The project was completed in 120 days with a crew of 25.



RAM Construction Services • 13800 Eckles Road • Livonia, MI 48150 • Tel 734-464-3800

The oldest and most experienced waterproofing and restoration specialty contractor in the U.S.

www.ramconstructionservices.com